BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/22/2020-21, Date:17.11.2020

SCHEDULE-B

NAME OF WORK: Removing of debris in ward no 13 Shettyhalli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor ~~Sri Sandesh H M~~ AMARAPPA.B	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the direction of Engineer-in-charge of the work.	Cum	665.40	165.6	Rupees One Hundred Sixty Five and Sixty Paise Only
2	Removing And Refixing stone slabs of drains and pointing in C.M (1:3) complete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	1905.12	157.36	Rupees One Hundred Fifty Seven and Thirty Six Paise Only
3	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges,curing and concrtee finished surface on both sides etc,and ccomplete as per specifications and as per the direction of Engineer-in-charge of the work.	Sqm	211.68	1573.57	Rupees One Thousand Five Hundred Seventy Three and Fifty Seven Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division, Bengaluru-73.

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.